



State of New Hampshire
DEPARTMENT OF NATURAL & CULTURAL RESOURCES
DIVISION OF PARKS & RECREATION

172 Pembroke Road Concord, New Hampshire 03301
Phone: 603-271-3556 Fax: 603-271-3553
TDD Access: Relay NH 1-800-735-2964
nhstateparks.org



ADDENDUM No.2

MOLLIDGEWOCK STATE PARK NEW VISITOR RECEPTION CENTER

Project No. ARP 2413

June 14, 2024

To: ALL CONTRACT BIDDERS

This addendum forms a part of the Contract Documents and modifies the Bidding Documents dated May 8, 2024, with clarifications as noted below. Acknowledge receipt of this addendum in the space provided in the Bid Proposal Form. Failure to do so may disqualify the Bidder.

1. Question: Detail 3 on Sheet A3.01 includes a note: "Wall Finish: FRP sheets on 5/8" Densglass Moisture and Mold Resistant Drywall." However, the Finish Schedule on Sheet A6.01 lists the wall finish material for rooms 104, 105, 107 & 108 as "FRP on 5/8" GWB." What is the intended wall finish material for rooms 104, 105, 107, & 108?

Answer: Abuse and moisture resistant drywall as per specification Section 09 21 16 / 2.01 C is to be used on all walls except the Utility Chase where the framing is open. In rooms 104, 105, 107 & 108, it will be the substrate for FRP.

2. Question: The siding material is called out as pine board and batten. Is there an option to use Engineered Wood Siding as per Specification Section 07 46 23 / 2.04?

Answer: The siding material is 1 x 12 pine board and 1 x 3 pine batten. The engineered wood siding will not be used on this project.

END OF ADDENDUM No.2