



# **MOUNT SUNAPEE**

## **Mount Sunapee Resort Annual Operating Plan 2014 - 2015**

May 15, 2014

*Prepared for:*  
NEW HAMPSHIRE DEPARTMENT OF  
RESOURCES AND ECONOMIC DEVELOPMENT

*Prepared by:*  
MOUNT SUNAPEE RESORT

# Mount Sunapee

## Annual Operating Plan

### 2014-2015

---

May 15, 2014

*Prepared for:*

The State of New Hampshire  
Department of Resources and Economic Development

Prepared by:

*Mount Sunapee Resort*

# Table of Contents

<b>INTRODUCTION</b>	3
<b>SECTION A</b> RECREATIONAL ACTIVITIES AVAILABLE TO THE PUBLIC	4
<b>SECTION B</b> SKI LIFT OPERATIONS	14
<b>SECTION C</b> SNOWMAKING and GROOMING OPERATIONS	15
<b>SECTION D</b> SKI SUPPORT SERVICES	16
<b>SECTION E</b> MAINTENANCE PROCEDURES	18
<b>SECTION F</b> SECURITY PROCEDURES	21
<b>SECTION G</b> EMERGENCY OPERATING PLAN	22
<b>SECTION H</b> STATUS OF SPECIAL USE PERMITS and LEASES	23
<b>SECTION I</b> MARKETING and ADVERTISING	25
<b>SECTION J</b> ENVIRONMENTAL MANAGEMENT PROGRAM	26
<b>SECTION K</b> SIGNAGE	32
<b>SECTION L</b> UTILITIES and ROADS	33
<b>SECTION M</b> IMPLEMENTATION OF THE MASTER DEVELOPMENT PLAN	34
Previously approved improvements from previous AOPs	35
Improvements in the 2014-2015 Annual Operating Plan	36
Ski trail improvements	36
Chair lift improvements	36
Building improvements	36
Snowmaking improvements	36
Infrastructure improvements	36
Other improvements: Summer Recreational Program	36
<b>MAP:</b> AOP 2014 topographical map	
<b>APPENDIX:</b> NH-DRED “Summer Recreational Program Proposal” November 3, 2011	

# INTRODUCTION

The *Lease and Operating Agreement* (the Agreement) originally dated April 30, 1998 between the State of New Hampshire Department of Resources and Economic Development (DRED) and Okemo Mountain, Inc., which was assigned by The Sunapee Difference, LLC as successor to Okemo Limited Liability Company f/k/a Okemo Mountain, Inc. to CNL Income Mount Sunapee, LLC on December 5, 2008, requires that the Operator (The Sunapee Difference, LLC d/b/a Mount Sunapee Resort) present an Annual Operating Plan to DRED each year for the term of the Agreement.

Paragraph 5 in the *Lease and Operating Agreement* defines the Annual Operating Plan requirements as follows:

## 5. ANNUAL OPERATING PLAN

“On or before the 15<sup>th</sup> of May during each year of this Agreement, the Operator shall submit to DRED an annual operating plan, including a schedule of the proposed days and hours of operation for the ski area, and a description of the types of recreational activities available to the public. The proposed schedule of operation shall be reviewed by DRED and either approved as proposed, or revised for resubmission. DRED shall notify the Operator in writing of a final schedule of operations no later than June 30<sup>th</sup> of each year. No changes in the days of operation or the scheduled hours of operation may be made without the prior approval of DRED. The Leased Premises shall not be closed to the public except for emergency or unsafe weather conditions.

The Annual Operating Plan shall describe in detail the following operations:

- a. Types of recreational activities available to the public
- b. Ski lift operations
- c. Snowmaking and grooming operations
- d. Ski support services
- e. Maintenance procedures
- f. Security procedures
- g. Emergency operation plan
- h. Status of special use permits and leases
- i. Marketing and advertising
- j. Environmental management program
- k. Signage
- l. Utilities and roads
- m. Implementation of Master Development Plan improvements.”

In the following sections, Mount Sunapee Resort (hereafter, “Mount Sunapee”) presents its Annual Operating Plan for 2014-2015 in accordance with the requirements of the Agreement.

## **SECTION A RECREATIONAL ACTIVITIES AVAILABLE TO THE PUBLIC**

### **Non-Skiing Activities**

In the summer of 2012, Mount Sunapee developed its summer Adventure Park as described in its *“Summer Recreational Program Proposal”* presented to the New Hampshire Department of Resources and Economic Development on November 3, 2011, and included again as an appendix in this 2014-2015 Annual Operating Plan.

In the summer of 2012, Mount Sunapee began building the following new recreational activities:

1. Canopy Zip Line Tour
2. Aerial Adventure Park (now called Aerial Challenge Course)
3. Mountain Bike Trails
4. Disc Golf
5. Interpretive Hiking Trails
6. Segway Tours
7. Miniature Golf

In the summer of 2013, Mount Sunapee added two additional challenge loops to the Aerial Challenge Course and continued work on the Interpretive Hiking Trails.

Our “Acro-Bag” which is a 50’x50’ air bag used in freestyle skiing training in winter was added to the Adventure Park for a Summer Freestyle Training Camp.

In the summer of 2014 Mount Sunapee proposes to add two new activities to the Adventure Park.

A Climbing Wall tower will be added which will also be a Gravity Jump platform into the Acro-Bag when the Freestyle Training Camps are not in session.

A “Mining Sluice” activity is a new feature designed for children ages 4 – 12. Small bags of “mining material” are purchased, and the children screen the contents of the bag in the water sluice to find gemstones and fossils. The mining sluice is a self-contained, recirculating water sluice.

The above summer Adventure Park activities are designed to appeal to a broad cross-section of guests with activities for all age groups, skill sets and price points.

In the May 2014 issue of Yankee Magazine, the Mount Sunapee Adventure Park was given an Editor’s Choice Award for the “Best Obstacle Course” in New England.

In the Appendix, the AOP 2014 Map shows the location of the Adventure Park activities.

In addition to Adventure Park, Mount Sunapee offers the following summer, non-skiing activities:

1. League of New Hampshire Craftsmen's Fair
2. Sunapee Lions Club Car Show
3. Weddings, Receptions, Banquets & Meetings
4. Summer Dinners
5. Events and Concerts
6. Summit Chairlift Rides
7. Summer Freestyle Skiing Camps
8. Recreational Hiking

### **CANOPY ZIP LINE TOUR**

The Canopy Zip Line Tour (CZLT) is located in the woods at the South Peak area.

Participants register in the Adventure Park Welcome Center building. They are then fitted with a safety harness and helmet, and have a safety presentation on their equipment and the course. They then ride the Clipper Ship Quad chair lift to the top of the CZLT course.

There are eight (8) different zip line stages and other features such as aerial bridges and rappels from a high tree platform to a lower tree platform. The final stage ends behind the Adventure Park Welcome Center Building with a rappel from the final aerial platform down to ground level.

A CZLT tour takes approximately two and one-half (2.5) hours to complete. The wire ropes on the first six stages in the woods are plastic coated for a quieter experience in the woods.

A full tour consists of eight (8) guests with two (2) guides. Two tours can depart per hour, on the hour and on the half-hour. This yields an hourly capacity of sixteen (16) guests and a daily capacity of ninety-six (96) guests. Guests are encouraged to make advance reservations for a specific day and time for their canopy tour experience due to the low daily capacity.

There are weight restrictions for users of the CZLT. Typically, eighty (80) pounds is the minimum weight and two hundred sixty (260) pounds is the maximum weight.

### **AERIAL CHALLENGE COURSE**

The Aerial Challenge Course (ACC) is located in the woods at South Peak adjacent to the base terminal of the Clipper Ship Quad chair lift.

The ACC is a ropes challenge course featuring four (4) layouts of differing skill levels that progress from novice to intermediate to advance.

The Aerial Challenge Course has a lower minimum weight restriction than the Canopy Zip Line

Tour. The minimum weight of fifty (50) pounds in the ACC will allow younger children who are unable to use the Canopy Tour Zip Line to use the ACC.

The participants in the ACC wear helmets and safety harnesses at all times, and are always clipped-in on the safety wire rope. Guides are present in the ACC during all hours of operation.

## **MOUNTAIN BIKE TRAILS**

Mount Sunapee plans to build a network of Mountain Biking trails that will appeal to families with an emphasis on intermediate trails from the summit of the South Peak area.

The Clipper Ship Quad chair lift can be fitted with racks to transport bicycles uphill on the chairlift to the start of the trail network.

## **DISC GOLF**

An 18-hole Disc Golf Course was constructed in the summer of 2012. The layout features holes that traverse ski trails and holes that are in the woods on the western side of the South Peak area. Disc Golf equipment is available for rent in the Mount Sunapee Adventure Center.

## **INTERPRETIVE HIKING TRAILS**

Mount Sunapee is completing a network of Interpretive Hiking Trails in collaboration with the Upper Valley Trails Alliance that will feature informational signage describing the local flora and fauna including the following:

- Mammals and Amphibians
- Birds and Butterflies
- Trees and Wildflowers
- Historical Sites and Local history

At the trail head for the Interpretive Hiking Trails, a large sign will illustrate the trail layout and show the locations of other wildlife signage and benches.

Guests may hike on the Interpretive Hiking Trails free of charge, and can enter the walking trail network at any location by foot. Guests may choose to ride uphill on the Clipper Ship Quad chair lift and start at the top of the Interpretive Trail for a small fee.

Sections of the hiking trails that do not cross ski trails may become part of the snow shoe trail network in the winter. Hiking trails which cross ski trails will be closed in the winter.

## **SEGWAY TOURS**

Segway PTs, or Personal Transporters, have become popular for touring historical sites and districts in major cities such as Boston, MA and Manchester, NH.

Mount Sunapee offers Segway PT excursions around the base area of the mountain in areas of relatively flat terrain. Our Segways have large, knobby tires for off-road use. Riders travel through wooded areas and ski trails in the base area and across parking lots 2 and 3. A typical Segway Tour is 75 minutes with 6 riders and a guide. The daily capacity is 30 to 36 guests.

All riders start with an indoor safety training session followed by a practice course training session before going on the Segway Tour. Helmets are provided for all participants.

## **MINIATURE GOLF**

During the summer of 2012, Mount Sunapee constructed an 18-hole Miniature Golf course at the base of the South Peak ski trails near the Clipper Ship Quad chair lift.

The Miniature Golf course has lights for twilight and early evening play until 10:00pm.

Landscaping for the Miniature Golf Course is perennial plants complimented by three small scale model wooden replicas of the Lake Sunapee Lighthouses. Man-made snow covers the course during the ski season.

## **MINING SLUICE**

Mount Sunapee proposes to add a "Mining Sluice" from the Cold River Mining Company this summer for children from age 4 to 12. The children purchase small bags of mining material and use a screen box in the water sluice to find gemstones and fossils.

The Mining Sluice is a self-contained, re-circulating water the system. The water touches only the leak-proof polycarbonate plastic insert in the sluice. The sluice will collect the mining ore which is kept out of the water tank by the baffle system, and is easily removed from the plastic insert.

## **CLIMBING WALL / GRAVITY JUMP - AIR BAG**

Mount Sunapee proposes to add a Climbing Wall tower which will also be a platform for Gravity Jumps into the 50 foot x 50 foot air bag. It will be located adjacent to the Aerial Challenge Course in the South Peak ski slopes area.

## **SUMMER FREESTYLE SKI TRAINING CAMP**

Mount Sunapee operates a “Summer Freestyle Ski Training Camp” during the second and third weeks of July. The Mount Sunapee Camp is a “day camp” with a maximum participation of thirty-two campers each week. Freestyle Camp activities are centered around freestyle ski training on the Acro-Bag and other Adventure Park activities.

## **DOG POLICY at Mount Sunapee**

Due to the extensive public operations in the summer and winter, dogs are not permitted to run loose at Mount Sunapee. Signs are posted informing our guests of this policy.

All dogs must be leashed and the owners must clean-up after their dogs. Mount Sunapee provides “Doggie Stations” with bags and disposal cans for the owners’ convenience.

Dogs are not permitted on the snow during the winter season, and must be on a leash when being walked in the parking lots.

## **THE FOLLOWING RECREATIONAL ACTIVITIES ARE AVAILABLE TO THE PUBLIC WITHOUT CHARGE DURING THE OFF-SEASON (May 1 – Oct 31):**

**Hiking** – In addition to the South Peak Interpretive Hiking Trails which are maintained by Mount Sunapee, other designated hiking trails such as the Summit Trail and the Lake Solitude Trail offer hiking on trails marked and maintained by the Sunapee-Ragged-Kearsarge Greenway and/or the Sunapee-Monadnock Greenway. These trails are part of a hiking trail network in the greater Sunapee region. Mount Sunapee does not operate, maintain, patrol or accept any liability for any individual(s) using these hiking trails.

In addition to the designated hiking trail network, Mount Sunapee currently allows hiking on the ski trails in the summer and fall. Mount Sunapee reserves the right to designate specific ski trails for hiking. Mount Sunapee reserves the right to not allow hiking on ski trails at its discretion.

**Walking** – Without undertaking a rigorous hike to the summit (the trail is over 7,000 feet long with over 1,400 feet of vertical rise) the expansive base area of Mount Sunapee allows visitors to take extended walks around the premises and stay on relatively flat ground.

**Bird Watching** – Mount Sunapee offers the avid birdwatcher an opportunity to see many bird species. With a variety of habitat including deciduous hardwoods and mixed conifers, wooded wetlands, open fields (ski slopes), streams, upland woodlands, ponds and lagoons; habitat exists for viewing many different bird species including summer residents and spring and fall migrants.

**Picnics** – Picnic tables and outdoor grills are available in the trees along Beck Brook near the South Peak area for use by the general public. Although trash cans are provided, Mount Sunapee encourages a “carry-in, carry-out” approach for personal trash.

**Restrooms** - The restrooms in the Adventure Center building are open 7-days a week from Memorial Day weekend through Columbus Day weekend.

The Sunapee Lodge facilities may not be open to the general public depending upon operating schedules and private event schedules.

The Summit Lodge is not scheduled to be open in the summer months, including use of the restroom facilities, except on days when the Summit chair lift is operating for the public.

**Parking** - Free parking is available for visitors to use the grounds for the above activities.

**Hunting & Trapping** – Mount Sunapee reserves the right to prohibit all hunting and all shooting activities of any type within ski area boundaries.

After the close of the Adventure Park activities in mid-October and prior to the ski area opening in November, Mount Sunapee may permit hunting and trapping within its lease area in accordance with New Hampshire Fish & Game Laws, Rules and Regulations.

Recreational shooting is not permitted within the lease area at any time.

**MOUNT SUNAPEE ALSO OPERATES THE FOLLOWING FEE BASED RECREATIONAL ACTIVITIES IN THE SUMMER AND FALL:**

**Summit Sky Rides** – Mount Sunapee will offer scenic chair lift rides to the summit on the Sunapee Express chair lift on selected summer weekends and selected fall foliage weekends. The lift may also operate during certain special events. A lift ticket is required to ride the chair lift.

<b><u>Summit Sky Rides schedule:</u></b>	<b><u>Date:</u></b>	<b><u>Chairlift operations:</u></b>
Lions Club Car Show	June 22	10:00am - 4:30pm
Pre-Craftsmen’s Fair weekend	July 26 – 27	10:00am - 4:30pm
Craftsmen’s Fair week	August 2 - 10	10:00am - 4:30pm
Fall Foliage Weekends	October 4-5, 11-13 and 18-19	10:00am - 4:30pm
Special events & functions	dates as booked	times as scheduled

**Note:** Chair lift operations and outdoor activities may be suspended or closed due to severe weather such as high winds, heavy fog, rain, thunderstorms, or other severe conditions.

**Food & Beverage Services** – Food and beverage services may operate in the Sunapee Lodge, the Spruce Lodge, the Summit Lodge and the Adventure Park Welcome Center during the summer for Adventure Park operations and for other special events and banquets & receptions as scheduled.

**Summer Dinners** – Mount Sunapee may offer evening dinners at both the summit and at the base of mountain during the non-skiing season. These dinners are by reservation only, and guests ride the Sunapee Express Quad chair lift uphill to the Summit Lodge for the dinners.

Many of the dinners are themed dinners such as Lobster Bakes and Family Fun Nights.

**Retail Ski Shop** – The retail shop in the Sunapee Lodge may operate in the summer and fall to provide accessories, light apparel and ski season closeout sales.

**Outdoor Concerts** – Mount Sunapee may offer country, classical, jazz, pop, rock or folk outdoor concerts in the late afternoon or early evening hours during the summer and fall. An admission fee may be charged for these concerts.

**Banquets & Receptions** – Facilities are available for catered private functions such as banquets, receptions, reunions, and special events from 8:00am until 11:30pm daily during the non-ski season. Wedding receptions and banquets are booked for most weekends. Fees are charged for the building rental and for food and beverage services rendered.

**Note:** During private functions any Base Lodge(s) may be closed to the general public.

**Shows, Fairs and Events** – Several shows, fairs and events may be scheduled at Mount Sunapee including, but not limited to, the following and their tentative dates:

- |  |                     |
|--|---------------------|
| 1.) Mountain Mucker Endurance Challenge      | May 31, 2014        |
| 2.) Sunapee Lions Club / Antique Car Show    | June 22, 2014       |
| 3.) League of New Hampshire Craftsmen's Fair | August 2-10, 2014   |
| 4.) October Fall Foliage Pig Roast           | October 11-12, 2014 |

## **Winter Activities**

### **ALPINE SKIING & SNOWBOARDING**

The principal winter recreational activity at Mount Sunapee is alpine skiing and snowboarding, and the ancillary services associated with alpine ski area operations.

Ancillary services include, but are not limited to, the ski school, children's ski school, childcare, ski and snowboard rental and repair shop, ski retail shops, food and beverage operations, alpine ski racing and freestyle skiing programs.

All users of Mount Sunapee's lifts and ski slopes are required to purchase either a daily lift ticket or a season pass in order to use either the ski lifts or the ski slopes.

Mount Sunapee offers downhill skiing and snowboarding on a variety of ski slopes and trails for all ability levels and interests. Additionally, Mount Sunapee also offers skiing in designated wooded areas or "glades" between certain ski trails.

Mount Sunapee also builds and maintains several terrain parks that contain jumps, rails, and snow features for all ability levels of snowboarders and skiers.

In addition to the named ski trails and glades as shown on the Mount Sunapee Trail Map, which are skied and maintained by the ski patrol and mountain operations staff, Mount Sunapee also allows "boundary to boundary" skiing within the ski area boundary as shown on the Trail Map. Areas not designated on the Mount Sunapee Trail Map as a named ski trail or gladed area are not patrolled or maintained by Mount Sunapee.

Any individual skiing or snowboarding in any area that is not a named and designated ski trail or glades on the Mount Sunapee Trail Map does so solely at their own risk with the understanding that these areas are neither maintained nor patrolled by Mount Sunapee. They may be responsible for the cost of rescue if injured or lost in these areas.

In January 2014, Mount Sunapee introduced an "Uphill Travel Policy" which allows skiers to hike uphill on designated trails from January 2 through closing day during non-holiday periods. Uphill Travel is permitted between the hours of 7:00am to 9:00am and between 4:30pm to 9:00pm. Regardless of where you are at 9:00am Monday through Friday, or at 8:00am Saturday and Sunday, you must head downhill at that time. Downhill travel is only permitted on open trails and slopes.

No Uphill Travel is allowed during the ski area operating hours of 9:00am to 4:30pm Monday through Friday, and 8:00am to 4:30pm on Saturday and Sunday, and during the night from 9:00pm to 7:00am. This policy is for the safety of all guests and employees.

Mount Sunapee allows alpine skis, telemark skis and snowboards on the slopes. Many other "sliding devices" exist for sliding on snow including snow bikes, snow trikes, snow balls, snow sleds and toboggans, etc. These devices are not permitted on the slopes at Mount Sunapee.

Snowmobiles are not allowed on Mount Sunapee except by Mount Sunapee maintenance and operations personnel using snowmobiles owned and maintained by Mount Sunapee. Snowmobile operation by the general public is strictly forbidden at all times.

**WINTER OPERATING SCHEDULE**

Mount Sunapee is open for alpine skiing and snowboarding seven days a week from the opening day of the ski season until the closing day of the ski season unless severe weather conditions force the mountain to be closed temporarily.

With favorable temperatures for early season snowmaking, Mount Sunapee plans to open for the winter season on November 28, 2014, the Friday after Thanksgiving Day, and plans to remain open through Sunday, April 12, 2015, weather permitting.

Because of the weather dependent nature of the ski business these dates are subject to change including: opening sooner or later and closing sooner or later, or both. In general, Mount Sunapee historically opens as soon as possible following Thanksgiving Day, and stays open until the first or second Sunday in April.

<u>LEASE YEAR</u>	<u>SKI SEASON</u>	<u>OPENING DATE</u>	<u>CLOSING DATE</u>	<u>DAYS OPEN</u>	<u>SKIER VISITS</u>
1	1998-1999	December 11	April 11	122	165,000
2	1999-2000	November 25	April 02	133	189,000
3	2000-2001	November 23	April 22	151	258,000
4	2001-2002	December 10	April 07	122	231,000
5	2002-2003	November 29	April 13	136	272,000
6	2003-2004	December 04	April 11	130	229,000
7	2004-2005	December 05	April 10	127	257,000
8	2005-2006	November 25	April 03	130	234,000
9	2006-2007	December 06	April 22	137	230,000
10	2007-2008	November 23	April 20	150	280,000
11	2008-2009	November 28	April 05	124	273,000
12	2009-2010	December 08	April 08	122	265,000
13	2010-2011	November 30	April 10	132	288,000
14	2011-2012	December 11	March 22	104	214,000
15	2012-2013	November 30	April 14	134	255,000
16	2013-2014	November 29	April 13	136	254,000

Operating hours for the ski lifts during the ski season are generally from 9:00am to 4:00pm midweek, and from 8:00am to 4:00pm on weekends and midweek holidays. Lodges generally open one hour prior to the opening of the lifts each day.

Dogs are not permitted on the snow at the ski area during the ski season. Any dog being walked in the parking areas must be on a leash.

Special events are held throughout the ski season including popular late season events such as the SpringFest concert, Slush Cup and Cardboard Sled Race in March and April.

Après-ski entertainment is offered in Goosefeathers Pub on weekends & holidays. Goosefeathers Pub is open from 11:00am to 6:00pm, or earlier or later for functions.

## **SNOWSHOE TRAILS**

In addition to alpine skiing and snowboarding, designated snowshoe trails may be available to the public.

The snowshoe trails are dependent upon natural snowfall and are not groomed or maintained. Users of the snowshoe trails assume all risk and personal responsibility for their usage of the trails.

A lift ticket is not required to use the snowshoe trails and there is no fee for using the snowshoe trails. Snowshoe rentals are available in the Mount Sunapee Ski Rental Shop.

Snowshoeing is not permitted on any ski slopes or trails at any time unless specifically approved by Mount Sunapee management.

## **NEHSA**

The New England Handicapped Sports Association (NEHSA) is based at Mount Sunapee, and begins their ski instruction and skiing assistance programs for adaptive skiers in early December and continues into late March or early April.

NEHSA is an independent organization and has a lease agreement with the Department of Resources and Economic Development.

Mount Sunapee provides the NEHSA organization with lift tickets and season passes for their volunteers, and electricity, water and wastewater disposal for their building.

NEHSA provides approximately 1,000 ski lessons per year for adaptive skiers.

## SECTION B SKI LIFT OPERATIONS

Mount Sunapee operates aerial chair lifts and surface lifts for winter alpine skiing and snowboarding in accordance with the American National Standards Institute (ANSI) – B77.1 National Code for Aerial Tramways, and the State of New Hampshire Department of Safety – Tramway Division - Rules and Regulations.

Supervision of lift operations and lift maintenance at Mount Sunapee is performed by experienced, qualified, full-time year round personnel.

Mount Sunapee currently operates six (6) aerial chair lifts and five (5) surface lifts.

<u>Aerial chair lifts</u>	<u>speed / design capacity</u>	<u>manufacturer</u>	<u>installation</u>
1.) Sunapee Express	1,100 fpm / 2,650 pph	Poma of America	1998
2.) Sun Bowl Quad	500 fpm / 2,400 pph	Poma of America	1998
3.) Clipper Ship Quad	425 fpm / 2,200 pph	Poma of America	2000
4.) North Peak Triple	450 fpm / 1,800 pph	Doppelmayr USA	1987
5.) Spruce Triple	425 fpm / 1,800 pph	Doppelmayr USA	1985
6.) Duckling Double	390 fpm / 900 pph	Roebing	1962

### Surface lifts:

1.) Piggy Back Tow	Borer	1994
2.) Rope Tow	SunKid	1996
3.) Little Carpet – 90’ moving carpet	SunKid	2000
4.) Flying Carpet – 340’ moving carpet	SunKid	2002
5.) Middle Carpet - 130’ moving carpet	SunKid	2010

### Scheduled hours of operation for ski lifts:

Weekends & Holidays	8:00am - 4:00pm
Weekdays	9:00am - 4:00pm

### Notes:

- 1.) Chair lift operations may be extended to 4:30pm on peak weekend days to alleviate traffic congestion by spreading out the exit time frame.
- 2.) Chair lift operations may begin prior to the regularly scheduled hours for private functions, alpine ski race course setting or other reasons.
- 3.) Adverse weather conditions, i.e., high winds, icing conditions, thunderstorms, etc. may affect chair lift operating schedules including delays and/or closures.
- 4.) Not all lifts are scheduled to operate seven days per week.
- 5.) SunKid moving carpets lifts were previously known as Bruckschlogl Lifts.

## **SECTION C      SNOWMAKING and GROOMING OPERATIONS**

### **SNOWMAKING OPERATIONS**

Snowmaking operations are scheduled to begin in mid-to-late November 2014 or as soon thereafter as sufficiently cold temperatures occur for productive snowmaking to begin. Snowmaking operations are planned for mid-November for Mount Sunapee to meet its goal of opening for the Thanksgiving weekend each year.

Snowmaking usually begins with nighttime operations in mid-November, and expands into around-the-clock snowmaking operations as temperatures become sufficiently cold during the day to rapidly expand snow coverage on the ski trails.

Snowmaking operations generally take place during the months of November, December, January, February and March, and have averaged approximately 700 hours per season for the past five (5) years. The 2013-2014 ski season began with favorable snowmaking weather in late November and early December. Snowmaking operations logged 670 hours last winter.

### **GROOMING OPERATIONS**

Snow grooming operations begin immediately after the start of snowmaking operations and prior to the opening day of the ski season. Grooming operations generally continue on a daily basis until the last day of the ski season.

Most ski trails are generally groomed every night although adverse weather conditions may affect grooming schedules. Some trails, i.e., ski trails with moguls such as Upper Flying Goose and Lift Line, and certain natural snow trails may not be groomed nightly or may not be groomed at all. Some advanced level ski trails (which are normally groomed) may not be groomed when natural snowfall allows for “powder” skiing days.

Snow grooming operations are generally performed between 4:30pm and 8:00am (during non-skiing hours) or on closed trails when grooming operations are necessary during the operating day.

Due to grooming operations being in progress at night, Mount Sunapee does not permit hiking on the mountain at night during the hours of 9pm to 7am in the winter season.

Mount Sunapee operates four (4) Prinoth 350 snow grooming vehicles for ski trail grooming. Each grooming vehicle is usually operated for two 8-hour shifts per night. The first shift grooms from 4:00pm to 12:00am, and the second shift grooms from 12:00am to 8:00am. A fifth Prinoth is used as a snowmaking utility vehicle.

## **SECTION D SKI SUPPORT SERVICES**

- 1.) **SKI SCHOOL** – Mount Sunapee offers a full service ski school operating daily from opening day until approximately April 1st when it closes for the season. The ski school is staffed by many PSIA certified directors, supervisors and instructors offering instruction to skiers and snowboarders of all ages and abilities including young children. Special package programs provide both the beginner and the experienced skier or snowboarder with lessons, rental equipment, and a lift ticket. Package prices will vary depending on the type and number of lessons. Guests may select a group lesson, a specialty clinic or a private lesson.
- 2.) **RENTAL AND REPAIR SHOP** – The ski and snowboard rental shop offers a large selection of current snowboards, shaped skis and snowshoe rentals. The ski rental shop is open every day that Mount Sunapee is open for skiing and riding. Mount Sunapee maintains a current inventory of quality rental equipment with all rental equipment inventory replaced on a normal rotational basis every three to four years.
- 3.) **SKI PATROL** – The Mount Sunapee Ski Patrol consists of a paid, full-time, professional core of supervisors and patrollers supplemented by paid part-time weekend patrollers, and part-time weekend volunteer patrollers. Ski Patrol members are expected to meet, as a minimum, the Outdoor Emergency Care requirements as administered by the National Ski Patrol. The OEC certification is the equivalent of a basic EMT certification. A 2-day refresher clinic is held the first week of November, and all Ski Patrol members and candidates are expected to attend. Currently, four (4) medical doctors serve as advisors to the Mount Sunapee Ski Patrol. Newport Ambulance provides Mount Sunapee with on-call ambulance transportation service to New London Hospital.
- 4.) **RETAIL SKI SHOPS** – Mount Sunapee operates retail ski shops in both the Sunapee Lodge and the Spruce Lodge. The Sunapee Lodge Ski Shop offers the latest ski and snowboard apparel in addition to accessory items. The Sunapee Lodge Ski Shop is generally open whenever the Sunapee Lodge is open during winter operations. The Spruce Lodge Ski Shop has reduced hours during early season and late season.
- 5.) **FOOD & BEVERAGE SERVICES** – All Culinary operations are operated by Mount Sunapee management and staff, and are not contracted to outside vendors (except for the Waffle Cabin). Food & Beverage services are located in the Sunapee Lodge, the Spruce Lodge, Goosefeathers Pub, and the Summit Lodge. Food & Beverage services generally operate seven days a week during the ski season from the

opening day through the closing day of each season. In the early and late season only one lodge with F&B may open based on business volumes.

Very few evening functions are booked by the Mount Sunapee Culinary staff during the winter season. Due to the demands of running a seven-day a week ski area operation in three lodges, Mount Sunapee generally does not accept winter bookings for private culinary events from December 10 to April 30 each year.

At all times, summer or winter, Mount Sunapee reserves the right to deny any group or organization the use of Mount Sunapee facilities.

Mount Sunapee does not permit guests to use outside food caterers to serve food or provide their own catering services in any of our licensed food establishments.

- 6.) **ENTERTAINMENT** - During the winter ski season, après-ski entertainment is offered on weekends and holidays in the Goosefeathers Pub of the Spruce Lodge. Beer, wine and spirits are served in Goosefeathers Pub to adults ages 21 and older.
- 7.) **ALPINE RACING PROGRAM** - Competitive training programs for youths, ages 5-19, offer season long instruction in alpine ski racing, freestyle skiing and snowboarding.
- 8.) **PARKING OPERATIONS** - Parking operations at Mount Sunapee are under the supervision of full-time year round staff at Mount Sunapee with part-time seasonal attendants assisting.
- 9.) **SHUTTLE SERVICES** - Mount Sunapee operates eight (8) shuttle buses which are converted school buses to give courtesy rides to skiers from Lot 3 to the two base area lodges. Also, two (2) one-ton trucks with open air, passenger-standing shuttle bodies transport skiers from the Spruce Lodge area and the Spruce Lodge Ski Rental shop to the South Peak novice slopes and the Sunapee Lodge.
- 10.) **WAFFLE CABIN** - Mount Sunapee has contracted with “Waffle Cabin” for a ten foot by fourteen foot cabin located on the snow near the Sunapee Lodge during the winter months. The “Waffle Cabin” is a temporary building that serves hot, fresh, Belgian style waffles dipped in chocolate. “Waffle Cabin” operates thirteen (13) “Waffle Cabins” across New England ski resorts including two others in NH. Okemo VT has two “Waffle Cabin” locations with the first one installed six years ago.

Mount Sunapee does not allow any independent operators, agents, groups or individuals to provide services for hire on the Mount Sunapee Resort premises without written approval or contractual agreements from Mount Sunapee Resort management. This includes, but is not limited to, independent ski instructors, race coaches, photographers, food vendors, rental companies, ski tuners, transportation services, retailers, real estate agents, fundraisers, etc.

## **SECTION E      MAINTENANCE PROCEDURES**

Maintenance operations are generally divided into five (5) departments to supervise and perform the required maintenance tasks at Mount Sunapee. Even though these specific departments exist, due to Mount Sunapee's small size there is considerable teamwork and cooperation working together among the maintenance departments.

**Buildings and Grounds** – The maintenance of the buildings and lodges at Mount Sunapee are under the supervision of a full-time year-round Base Operations Manager who performs regular inspections of all facilities. Custodial and cleaning operations are performed daily. Building repairs and maintenance work is performed as needed.

Security operations are under the direction of the Base Operations Manager and the Buildings & Grounds Supervisor. Summer lawn mowing in the base area is under the supervision of the Buildings & Grounds Supervisor.

**Vehicle Maintenance** – The Vehicle Maintenance Supervisor is responsible for the service and maintenance of all vehicles at Mount Sunapee. Daily and/or weekly inspections are performed, and repair work is performed as needed. The track vehicle fleet including snow grooming vehicles and construction equipment is also maintained under the direction of the Vehicle Maintenance Supervisor.

**Lift Maintenance** – The Lift Maintenance Supervisor and Mountain Manager are responsible for the maintenance of the six (6) chair lifts and five (5) surface lifts.

Service and maintenance is performed on each lift during the off-season in accordance with the Lift Manufacturers' Service Manuals and by ANSI B77.1 code.

Prior to operating any chair lift for the winter ski season or for the summer season, each lift is inspected by personnel from the NH Tramway Division and by representatives from our insurance carrier.

During the operating season, chair lifts are inspected daily and are ridden by Mount Sunapee maintenance staff to observe the alignment of the sheave trains and haul rope.

**Trail Maintenance** – Ski trail maintenance is performed during the ski season and the off-season under the direction of the Mountain Manager, the Ski Patrol Director and the Grooming Supervisor. In-season trail maintenance work generally includes snow grooming operations and slope safety inspections.

Off-season work includes erosion control, water bar repairs, seeding & mulching, trimming sapling growth back on trail edges, mowing trails and general preparations for the next ski season.

**Snowmaking Maintenance** - Snowmaking maintenance during the ski season and during the off-season is under the supervision of the Snowmaking Supervisor and the Mountain Manager.

**Maintenance Best Management Practices** – Best management practices in Mount Sunapee’s maintenance operations have been implemented for many years. We constantly strive to evolve and improve our best management practices.

Many of these best management practices have been adopted from the Federal EPA and/or NH-DES best management practices guidelines. Some of our many BMPs are listed below.

The sand/salt mixture for sanding roads and parking lots in the winter is stored in an enclosed three-sided building with a concrete floor. Any spillage during unloading or loading operations is scooped up and returned to the sand pile inside the enclosed building.

In the vehicle maintenance shop, all wash water from the floor drains goes through two separation chambers, a solids separator and an oils separator, before being piped into the waste water lagoons. The separation chambers are pumped twice annually by professional firms that are licensed for the proper disposal of such refuse.

In the vehicle maintenance shop, all oils, lubricants and solvents are stored indoors year-round. All parts washing basins that are solvent based are internally re-circulating fluid devices with no solvents released from the closed system.

Procedures are in place advising the maintenance staff about the proper use of solvents.

Fuel storage tanks have electronic monitoring systems and are manually monitored by Mount Sunapee staff.

As a standard best management practice, any vehicle or piece of equipment that shows any sign of a fluid leak is immediately removed from service and the leak is repaired.

Most waste oils and fluids such as anti-freeze are stored indoors in 55 gallon drums until picked up by licensed professional firms for proper disposal. There are two 275 gallon outside waste oil tanks. These tanks are not filled outdoors, but have inlet pipes coming from inside the maintenance shop. Waste oils and waste fluids are disposed of promptly when the designated container is 80% full.

Mount Sunapee has invested in emergency spill containment kits and has developed spill response procedures. Staff is trained in the procedures to immediately deal with spills. Each building has its own dedicated yellow 55-gallon emergency spill containment kit.

The emergency spill kits consist of booms to encircle and contain the spill zone and absorbent material designed specifically to absorb the spilled fluid. After clean-up, the contaminated materials used in the clean-up are placed in the 55 gallon container, and the

container is picked up by a professional firm licensed for the proper disposal of such refuse.

All paints and solvents are stored indoors. Empty containers are picked up by a professional firm licensed for proper disposal each fall, as required, following the summer maintenance season.

Used tires and used batteries are stored indoors for brief periods of time until picked up by licensed professional firms for proper disposal.

All agricultural products such as hay, seed and fertilizer are stored indoors year-round.

Very few pesticides are used at Mount Sunapee and those that are used are stored indoors and are used according to the label instructions for approved uses. Mount Sunapee typically uses professional firms to spray building eaves for cluster flies and other pests annually.

Erosion control silt fencing and staked hay bales are used around the perimeter of any disturbed areas of soil during construction and/or maintenance operations.

Drainage ditches have stone check dams to reduce the velocity of storm water run-off and to create sediment settling areas. These check dams are regularly cleaned and maintained.

Level spreaders and swales are also used to reduce storm water run-off and to create sediment settling areas. These areas are regularly cleaned and maintained.

On the wastewater lagoons, regular mowing is done on the berms and sides of the dams to prevent sapling root growth into the banks of the dams.

Safety Data Sheets (SDS) are maintained for all chemicals used at Mount Sunapee, and all staff receives orientation training on the availability of SDS information.

## **SECTION F      SECURITY PROCEDURES**

Mount Sunapee maintains a staffing schedule to provide a general presence and surveillance on the facilities during the winter ski season, the summer season and during the off-seasons.

Mount Sunapee works closely with the Newbury Police Department to maintain a presence at Mount Sunapee during selected events. The Newbury Police Department also provides random drive through patrols of the premises.

Mount Sunapee has installed security cameras inside and outside of our base lodges and maintenance buildings to provide surveillance of the premises, internally and externally. For each of the past four (4) years, additional security cameras have been added for security purposes.

Mount Sunapee's security priorities are specified under the following headings:

**Safety of our Guests** – Mount Sunapee endeavors to provide a safe, secure and enjoyable environment for our guests and our staff. Operating procedures, project planning and staffing are performed in a manner to minimize threatening situations such as physical harm or theft of personal property or any other forms of endangerment to our guests.

**Prevention of Theft of Equipment** – Operational policies and staffing schedules are done so as to minimize theft of equipment and other personal items.

**Prevention of Vandalism** - A security program utilizing Mount Sunapee staff members and building security alarm/motion detection systems safeguard the buildings against off-hours vandalism.

Mount Sunapee has added security cameras as part of our security program, and will continue to add more security cameras in the future.

**Prosecution of Criminals** – Individuals responsible for criminal acts at Mount Sunapee will be prosecuted as provided by New Hampshire law and Federal law.

## **SECTION G      EMERGENCY OPERATING PLAN**

The Emergency Action Plan for Mount Sunapee consists of plans for dealing with emergency events at the ski resort. In the event that an emergency situation requires the involvement of an outside agency, i.e., Local Police, State Police, Fire Department, Fish & Game Department, the General Manager and the appropriate Mount Sunapee employees will assist the outside agency in responding to the emergency situation.

While the plan is designed to be flexible and applicable to all major emergencies, the following procedures should be followed:

- Local Fire and Police Departments will be notified about any unusual situations at Mount Sunapee. There may be times when a call will be made to an outside agency to make them aware of a situation although not requiring immediate assistance.
- The following Mount Sunapee management team members will be contacted: President, General Manager, Base Operations Manager, Mountain Operations Manager, Marketing Director, and Building Maintenance Supervisor as required by the nature of the emergency situation.
- The emergency command post will be located in the administrative office unless otherwise designated.
- Only designated members of the management team will speak with the media.
- Mount Sunapee management has had several planning meetings with emergency management officials from the Town of Newbury in developing the Emergency Action Plan. The Town of Newbury, DRED and DES have copies of the plan.

## **SECTION H STATUS of SPECIAL USE PERMITS and LEASES**

Mount Sunapee currently has three (3) Special Use Permits from the New Hampshire Department of Resources and Economic Development (DRED), and certain operating agreements and contracts with outside vendors and third parties as detailed below:

### **SPECIAL USE PERMITS:**

**1.) Special Use Permit for use of the Sun Bowl access road**

Purpose of Permit: Provide access to the base of the Sun Bowl area  
Period of Use: June 15, 2012 to May 31, 2015

**2.) Special Use Permit for parking use of the State Beach parking lot in winter**

Purpose of Permit: Staff parking and overflow parking for the resort  
Period of Use: June 15, 2012 to May 31, 2015

**3.) Special Use Permit for Mountain Bike Trail on Bowl Road**

Purpose of Permit: Mountain Bike Trail on Bowl Road  
Period of Use: June 15, 2012 to May 31, 2015

(In 2012, Mount Sunapee gave up its Special Use Permit for a storage area on the uphill side of the Access Road so that DRED could use that space as a work area for its Trails Division.)

**LEASES, CONTRACTS and AGREEMENTS**

1.) **League of New Hampshire Craftsmen** – The League of NH Craftsmen has an annual contract / lease agreement with Mount Sunapee to operate the annual Craftsmen’s Fair which always opens on the first Saturday in August and runs for nine (9) days.

Fair setup activities on the grounds of Mount Sunapee generally begin during the third week of July to prepare for the Fair opening in early August. The Craftsmen’s Fair is scheduled for August 2, 2014 through August 10, 2014 this year.

2.) **New England Handicapped Sports Association (NEHSA)** – Mount Sunapee has an operating agreement and a liability agreement with NEHSA.

3.) **On-Mountain Photography** – Mount Sunapee may enter into an annual contract and lease agreement with a service provider/concessionaire for space to operate a photography service at Mount Sunapee Resort during the winter ski season.

With the popularity of small, personal digital cameras and high-resolution cameras in personal cell phones, there has been minimal interest in an on-mountain photography service for the past 5 years.

4.) **Resort Real Estate Sales** – Mount Sunapee may enter into an annual contract and lease agreement with an outside company to provide real estate marketing, sales or rental services at Mount Sunapee Resort.

5.) **Waffle Cabin** - Mount Sunapee signed a three-year contract with “Waffle Cabin” for a ten (10’) foot by fourteen (14’) foot cabin to be located on the snow near the Sunapee Lodge during the winter months. The cabin is classified as a temporary structure, not a building.

The “Waffle Cabin” primarily serves hot, fresh, Belgian style waffles dipped in chocolate. The “Waffle Cabin” group operates thirteen (13) “Waffle Cabins” across New England ski resorts including two others in NH including Waterville Valley and Ragged Mountain. Okemo VT has two “Waffle Cabin” locations with the first installed six years ago.

## **SECTION I      MARKETING and ADVERTISING**

Mount Sunapee's marketing, advertising and sales are under the direction of a full-time year-round Director of Marketing & Sales. The Director of Marketing & Sales is responsible for branding and positioning Mount Sunapee in the competitive New Hampshire and New England ski industry.

Mount Sunapee will be prepared to host approximately 272,000 skier visits during the 2014-2015 ski season. We have averaged 267,000 skier visits during the five of the last six years (excluding the 2011-12 season which was an usually short season). Skier visits this past winter were 254,000 which is below our 5-year average due to an extremely cold January referred to as the "polar vortex" cold, and three winter thaws.

### **MARKETING**

Mount Sunapee is positioned as a "big mountain, family resort, close to home" with emphasis on providing consistently superior snow surface conditions, excellent guest services and excellent learn-to- ski programs.

### **ADVERTISING**

Mount Sunapee develops and produces collateral pieces and brochures including a group sales planner, a trail map, a ski school brochure, a magazine and other collateral materials. Mount Sunapee uses newspaper, Internet, radio, television and billboard advertising media to promote skiing, snowboarding and summer recreational activities at Mount Sunapee.

### **SALES**

In addition to the Director of Marketing, Mount Sunapee has a full-time year- round Sales Manager to book group business during the ski season and the off-season months.

### **PROMOTIONS & EVENTS**

Mount Sunapee schedules promotions and events throughout the ski season. Some of the more popular events are the "SpringFest Concert," the "Slush Cup" and the "Cardboard Sled Race" in late March and early April of each year.

### **TICKET PROGRAMS**

Mount Sunapee offers many diverse ticket programs and packages including season passes, daily lift tickets, multi-day lift tickets, learn-to-ski packages, group sales programs, corporate ticket programs and special promotional ticket programs.

## **SECTION J                      ENVIRONMENTAL MANAGEMENT PROGRAM**

Mount Sunapee presented its Environmental Management Plan as a required part of its Five-Year Master Development Plans. In this Annual Operating Plan, the areas of the Environmental Management Program that are discussed below are relative to the major resources utilized at Mount Sunapee or to the improvements planned in the current Annual Operating Plan for this summer.

### **A.)        WATER USAGE AND CONSERVATION**

Snowmaking – Mount Sunapee is permitted by the New Hampshire Department of Environmental Services to withdraw up to 258 million gallons of water from Lake Sunapee for snowmaking purposes during the winter season. Snowmaking water withdrawals have averaged 153 million gallons for the past five years, and 151 million gallons for the past 10 years.

Water conservation – Annual water conservation measures (such as low flush toilets) undertaken by Mount Sunapee since 1999 have been effective in reducing wastewater levels in the lagoons despite increased business volume.

In the summer of 2003, Mount Sunapee completed a phased renovation of the restrooms in the Spruce Lodge adding new single faucet, low-flow water fixtures.

In the summer of 2004, Mount Sunapee completed a project that reduced storm water run-off infiltration into the lagoons.

### **B.)        SEPTAGE DISPOSAL / TREATMENT**

Mount Sunapee operates a lagoon and spray field waste treatment system under the rules and regulations of the NH - Department of Environmental Services.

In May 2013, Mount Sunapee submitted its permit renewal application to the NH – Department of Environmental Services for operation of the lagoons and spray fields. The permit is valid for five (5) years until June 2018.

Mount Sunapee has retained Hoyle-Tanner Engineering Associates since 1998 for evaluation and permitting of the lagoons and spray fields, and they did the engineering analysis work for the permit renewal.

Septic tanks are generally pumped (septage) two (2) times per year by a licensed NH hauler to a sewage treatment plant. The tanks are usually pumped prior to the ski season, and once during the ski season.

Wastewater from the septic tanks flows to the lagoon system for secondary treatment, and is then pumped to a spray irrigation field in the woods above the lagoons for final polishing in the soil column.

In the summer of 2000, Mount Sunapee rebuilt the existing spray field pipelines, and installed metering to monitor the output of the spray field system.

Since the implementation of water conservation measures at Mount Sunapee in 1999, the total gallons of wastewater input into the lagoons has remained relatively constant despite the increase in skier visits during the past three years.

In the summer of 2006, Mount Sunapee Resort rebuilt the septic fields serving the Summit Lodge using the Presby Environmental System.

### **C.) DRAINAGE, EROSION AND WATER QUALITY ISSUES**

Mount Sunapee utilizes the New Hampshire Stormwater Manuals – volumes 1-3, published in December 2008 for guidance in managing storm water run-off, soil stabilization and erosion control practices.

Many erosion control buffers, swales, stone check dams and level spreaders are in place to reduce the velocity of storm water run-off and maintain water quality.

Each spring, sand from winter sanding operations is cleaned up in April by a machine designed for sweeping up sand from the parking lots and roadways. This spring clean-up prevents very fine sand particles from being washed into the brooks flowing from Mount Sunapee during spring rains and run-off.

Mount Sunapee also uses many best management practices in its maintenance operations to maintain the water quality in the streams flowing from the mountain.

In the vehicle maintenance shop, all wash water from the floor drains goes into two separation chambers, a solids separator and an oils separator, before being piped into the waste water lagoons. The separation chambers are pumped annually by licensed professional firms for proper disposal. These practices have been adopted from EPA guidelines for water quality.

**D.) SOLID WASTE DISPOSAL**

Purchasing discretion is used to reduce solid waste by avoiding or minimizing the use of certain packaging such as styrofoam and other products to minimize waste.

Recycling efforts have increased each year at Mount Sunapee since 1998. Recycling of glass bottles has been a standard practice since 2006-2007.

Mount Sunapee currently recycles glass bottles, glass light bulbs, plastic containers, cardboard, paper, aluminum cans, scrap metals, waste oils and kitchen oils.

In 2009, Mount Sunapee entered into a contract with our solid waste carrier, Casella Waste Services, to provide single-stream recycling at Mount Sunapee. We continue to research opportunities to expand our recycling program where feasible.

Recycled tonnage has grown from 8 tons to over 20 tons in the past three years. Trash tonnage has decreased as the quantity of recycled waste has increased.

**E.) AIR QUALITY AND TRAFFIC CONGESTION MITIGATION**

Mount Sunapee had a “State Permit to Operate,” # SP-0034, from the NH – Department of Environmental Services for the operation of four (4) stationary diesel air compressors used in snowmaking, and four (4) diesel emergency evacuation engines used in chair lifts. Mount Sunapee operated these diesel engines in compliance with State and Federal air emission regulations.

All four diesel air compressors that were originally permitted are no longer in service, and Mount Sunapee terminated its State Permit to Operate in January 2014.

On January 31, 2014, NH-DES issued a “General State Permit,” # GSP-EG-0427, to Mount Sunapee for the operation of the four diesel emergency evacuation engines used in its chair lifts.

Mount Sunapee used the State Beach for overflow parking eight (8) times during the 2013-2014 ski season.

The State Beach is used, on average, 4 to 5 times per year. In 2010-2011, the State Beach was used for overflow parking eleven (11) days, the most ever.

The overflow parking days generally coincide with peak holiday weekends of the winter season: December 28 – December 31; January 15-16; and, February 15-17.

Mount Sunapee works with the Town of Newbury Chief of Police on anticipated peak traffic days during the winter season.

**F.) FORESTRY MANAGEMENT**

The forested lands within the Mount Sunapee lease are not actively managed for timber harvesting or silviculture.

**G.) WETLANDS IMPACTS**

Wetlands at Mount Sunapee are regulated by Local, State and Federal rules, and Mount Sunapee complies with these rules and regulations in all proposed projects.

**H.) WILDLIFE HABITAT PRESERVATION**

Per 1986 NH Fish and Game Department mapping, no critical wildlife habitat areas were identified within the lease area. Improvements proposed in the current Annual Operating Plan would not affect critical wildlife habitat.

**I.) SCENIC AND AESTHETIC QUALITIES**

The Annual Operating Plan for 2014-2015 preserves the scenic and aesthetic qualities of Mount Sunapee by maintaining the general character of the area with the proposed summer recreational activities, and by maintaining the facilities for the alpine skiing experience in winter recreational activities.

The planning efforts and the choices of recreational activities in the proposed Summer Recreational Program are designed to be consistent with the natural setting and essential character of Mount Sunapee.

The winter recreational activities in this Annual Operating Plan are consistent with the recreational activities offered at Mount Sunapee prior to the Lease & Operating Agreement of April 1998.

**J.) RARE PLANT RESOURCES**

The NH Natural Heritage Inventory has identified a population of a threatened orchid, bog twayblade (*Liparis loeselii*), existing on the Duckling (Jet Stream) ski slope that is apparently perpetuated “in part by management of the open ski run.”

The work proposed in this Annual Operating Plan would not affect this plant population. Mount Sunapee will protect the population by mowing the trail after mid-August allowing time for flowering and seed dispersal.

**K.) ARCHAEOLOGICAL / HISTORICAL RESOURCES**

A previously unknown burial site from the 1700s has been located in the woods to the east of the South Peak ski slopes. The site is protected in an undeveloped area.

**L.) ENERGY CONSERVATION and MANAGEMENT**

**a.) Spruce Lodge boiler replaced**

In the summer of 2013, Mount Sunapee replaced the original 1962 boiler in the Spruce Lodge with two smaller boilers, operating in a two stage system. The new boilers are propane fired.

The two stage dual boiler system has resulted in greater energy savings due to the first stage operating when the load demand is less than 50%. The second stage kicks in when the load demand is greater than 50%. The original boiler was a 100% duty boiler operating at peak capacity at all times.

A 50% decrease in energy usage was achieved in 2013-14, and the two boiler system also provides system redundancy.

**b.) Fuel storage facility**

In the fall of 2011, Mount Sunapee replaced both of the underground, single-wall fuel storage tanks at the Service Shop. Originally installed in 1985, the 6,000 gallon gasoline tank and the 6,000 gallon diesel fuel tank were single wall tanks and had to be replaced before December 31, 2012 to meet state and federal regulations.

In November 2011, a new double-walled 12,000 gallon tank with an internal partition was installed to meet the state and federal regulations. A Veeder-Root fuel monitoring and alarm system was installed to monitor both partitions of the tank.

Engineering was provided by Horizons Engineering of Littleton, NH and plans were approved by NH-DES and a state permit issued for the new installation. A building permit was issued by the Town of Newbury.

The new fuel storage facility is now in full compliance with all State and Federal regulations for fuel storage facilities.

**c.) Bio-diesel fuels**

In the fall of 2007, Mount Sunapee changed fuel providers and began using bio-diesel fuel blends from Evans Fuel Company in its operations.

A bio-diesel B-5 blend was used in the #2 heating oil supplied for use in the base

lodges heating oil systems. In accordance with Federal EPA regulations, all diesel fuel is an ultra-low sulfur formation with less than 15ppm sulfur content.

**d.) Electrical Energy Efficiencies**

Mount Sunapee has completed the replacement of older fluorescent lighting ballasts with newer, energy efficient ballasts throughout the business in both public and non-public buildings. All new construction has energy efficient fluorescent lighting installed during construction.

In the summer of 2007, Mount Sunapee purchased the latest technology in energy efficient snow guns. Eighteen (18) new HKD SV-10 snow guns were added which operate more efficiently at higher temperatures than our current snow guns.

In the summer of 2008, Mount Sunapee purchased an additional thirty (30) new HKD SV-10 energy efficient snow guns.

In the summer of 2009, Mount Sunapee purchased an additional ten (10) HKD SV-10 energy efficient snow guns, and one (1) TechnoAlpin tower mounted fan gun.

In the fall of 2011, Mount Sunapee purchased another fourteen (14) HKD SV-10 energy efficient snow guns.

In the fall of 2013, Mount Sunapee purchased an additional fifty-two (52) HKD-SV10 Impulse snow guns which resulted in a savings of over 500,000 KWHs of electricity last season.

In the last six years, Mount Sunapee has purchased one hundred and thirty-nine (139) HKD SV-10s to replace older inefficient snowmaking guns.

The new SV-10 snow guns use only 25% of the compressed air as the older K3000 ground snow guns use resulting in significant annual energy savings.

**M.) STORM WATER POLLUTION PREVENTION PLAN**

Mount Sunapee has an internal Storm Water Pollution Prevention Plan for storm water pollution prevention measures and to use as a basis for improving best management practices. A Multi-Sector General Permit is not required by the Environmental Protection Agency for ski areas which are classified under the SIC 7011 code.

## **SECTION K      SIGNAGE**

Mount Sunapee believes that high quality, effective signage is important and continues to maintain and upgrade its resort signage each year. Our signs are designed to be informational, simple and consistent in design.

Design changes to the Mount Sunapee State Park entrance sign were approved by the NH DRED - Division of Parks, and the Town of Newbury in December 1999.

Also in 1999, Mount Sunapee completed the replacement of all the existing ski trail signage on the mountain with new ski trail directional signs.

In 2000, Mount Sunapee replaced the existing chairlift signage at the base of each chairlift and improved signage on the buildings.

A “*Courtesy Counts*” safety and skier courtesy program was launched at Mount Sunapee for the 2000-2001 ski season, and signage was placed on the chairlift towers and in the lodges promoting the concept of courtesy and safety on the ski slopes. This program is updated each year.

In the summer of 2008, Mount Sunapee renovated the main, large entrance sign at the traffic circle.

In the summer of 2014, Mount Sunapee will continue its upgrades of the resort’s signage to provide better information and directions for traffic and skier flow around the resort.

Signage for the Summer Recreational Program has been developed and placed in appropriate locations and we will continue to improve on our signage in both winter and summer operations.

Mount Sunapee plans to add indirect lighting to the large sign at the Route 103 entrance in accordance with the Town of Newbury’s sign regulations.

## **SECTION L UTILITIES and ROADS**

This section provides information on the parking areas, internal work roads, walkways, water supply and distribution, sewage disposal, electrical systems and telephone systems at Mount Sunapee. The following projects have been completed or are proposed:

- Phone System – A fiber optic cable was installed between the two base lodges and from the Spruce Lodge to the maintenance shop in the fall of 2001. A local area computer network was completed in 2000. A new phone switch and telephone system was installed in October 2005.

Wireless service for personal computers and hand held computers was installed at Mount Sunapee in January 2006.

Verizon Wireless upgraded the communications capabilities of the cellular tower at the summit in the fall and winter of 2011-12 by installing fiber optic cable from the base to the summit in preparation for LTE 4G technology service from the cell tower.

As a part of that upgrade, Mount Sunapee Resort has fiber optic connectivity in addition to the existing copper wire phone network. Also, “In-building” technology was installed in the Spruce Lodge in the fall of 2012 to improve the signal strength in this building.

- Deep Well – Well testing was performed in 1999 to determine the capacity of the primary source of potable water for Mount Sunapee. The well has significant water capacity that will meet the needs of Mount Sunapee for the foreseeable future.
- Electrical Transformers – Mount Sunapee has its electrical transformers checked annually by TSI, Inc. for maintenance needs and to assure their operational reliability.
- Parking Areas – All parking lots receive annual maintenance in the form of snow removal, trash clean up, and sand removal in the spring and drainage maintenance.
- Sewage Disposal – Engineering consultation with Hoyle-Tanner Associates continues for monitoring the wastewater inflows into the lagoons and for assuring that the capability of the lagoons is adequate for Mount Sunapee’s needs.

Hoyle-Tanner submitted our renewal application to the Department of Environmental Services for our Groundwater Discharge Permit in the spring of 2013 and we received our Permit GWP-198704058-N-005 on June 13, 2013. The permit is valid for five years, through 2018.

We are not planning to expand the spray fields at this time, and did not make application to do so in our permit renewal application.

## **SECTION M IMPLEMENTATION of the MASTER DEVELOPMENT PLAN (MDP)**

Mount Sunapee's first Five-Year Master Development Plan 2000-2004 was presented on January 25, 2000, and described capital improvements and plans for Mount Sunapee during the next five years.

Mount Sunapee's second Five-Year Master Development Plan 2005-2009 was presented on June 1, 2004, and described capital improvements and plans for Mount Sunapee for the next five to ten years.

Mount Sunapee's third Five-Year Master Development Plan 2009-2014 was presented on June 1, 2009, and described capital improvements and plans for Mount Sunapee for the next five to ten years.

This Annual Operating Plan 2014-2015 describes the MDP improvements proposed for Mount Sunapee during the spring and summer of 2014.

Mount Sunapee has invested over sixteen million in capital improvements during the first sixteen summers since July 1, 1998. This will be our seventeenth (17<sup>th</sup>) summer of capital improvements and capital maintenance projects at Mount Sunapee.

In the summer of 2014, new capital projects and capital maintenance projects are estimated to cost approximately \$1,500,000.

Mount Sunapee continues to work on designs for an extensive renovation of the Spruce Lodge, but the project is not planned for this summer.

Most of capital maintenance spending planned for the summer of 2014 will be to maintain or expand the existing facilities, equipment and inventories at Mount Sunapee.

The major new capital projects planned for this summer will be to replace the existing Sunbowl Quad chairlift with a high-speed Express Quad chairlift.

The secondary projects proposed for this summer include the addition of a Climbing Wall / Gravity Jump Airbag and a Mining Sluice in our summer Adventure Park.

Some capital improvement projects planned for Mount Sunapee have been presented and approved by the New Hampshire Department of Resources and Economic Development in Mount Sunapee's previous Annual Operating Plans, but have not been started yet.

Due to financial constraints, planning & permitting approvals, and/or time constraints some previously presented AOP projects will be carried over into this or into future Annual Operating Plans.

**Projects previously approved by the NH-Department of Resources and Economic Development in previous Annual Operating Plans:**

1.) SKI TRAIL IMPROVEMENTS

- Construction of a new ski trail – to the west of the Upper Ridge trail.
- Widen a section of Billy Goat trail (renamed Pipeline).

2.) SNOWMAKING IMPROVEMENTS

- Add snowmaking capability to new ski trails when constructed.
- Replace the existing South Peak snowmaking system on all trails.

3.) INFRASTRUCTURE IMPROVEMENTS

- Construct a new gravel parking lot #4 along the Access Road.
- Expand the spray fields for the septic system.

(None of the above previously approved projects will be undertaken in the summer of 2014 at Mount Sunapee Resort.)

**Improvements planned in the 2014-2015 Annual Operating Plan:**

**1.) SKI TRAIL IMPROVEMENTS**

- Maintenance projects.

**2.) CHAIR LIFT IMPROVEMENTS**

- Replace the Poma Sunbowl Quad fixed grip chair lift with a high-speed Poma Express Quad lift from Okemo

(project contingent on Okemo purchasing a new 6-passenger chair lift this year and relocating their existing lift to Mount Sunapee.)

**3.) BUILDING IMPROVEMENTS**

- Maintenance projects.

**4.) SNOWMAKING SYSTEM IMPROVEMENTS**

- Snowmaking system maintenance projects.

**5.) INFRASTRUCTURE IMPROVEMENTS**

- Upgrade primary power line from Maintenance Shop to the Sunbowl to 480volt, 3-phase power (currently, 200volt, single phase service.)

(project contingent upon installing Express Quad in the Sunbowl.)

**6.) OTHER IMPROVEMENTS – Summer Adventure Park projects**

- Install a Climbing Wall / Gravity Jump Platform in Airbag


Designed and installation by Phoenix Experiential Designs who have designed and installed Mount Sunapee's Canopy Zip Line Tour and Aerial Challenge Course.

- Install a Mining Sluice


Designed and built by Cold River Mining Company. This activity operates in the Adventure Park in the summer, and would be removed and stored away during the winter.

- Complete the Interpretive Hiking Trails in the South Peak Adventure Park.

- Develop Mountain Biking trails in the South Peak Adventure Park area.



**Climbing Wall / Gravity Jump**




**Climbing Wall / Gravity Jump**

## Proposed Mount Sunapee Mining Sluice





Editors' Choice — May/June 2014  
BEST OBSTACLE COURSE  
Mount Sunapee Adventure Park




- CLIMBING WALL
- GRAVITY AIR BAG JUMP
- FREESTYLE SKI TRAINING RAMP
- MINING SLUICE
- AERIAL CHALLENGE COURSE
- MINIATURE GOLF
- CANOPY TOUR ZIPLINE

MOUNT SUNAPEE RESORT OPERATOR  
 CLD CONSULTING ENGINEERS, INC. ENGINEERING  
 HOYLE, TANNER & ASSOCIATES, INC. WASTE WATER ENGINEERING

- EXISTING BUILDINGS
- EXISTING ROADS
- EXISTING PONDS
- EXISTING VEGETATION
- EXISTING LIFTS



IMPROVEMENTS PLAN 2014  
 May 7, 2014




AOP2014



NO.	DATE	REVISION	DESIGNED	CHECKED	APPROVED

**CLD CONSULTING ENGINEERS**  
 16 Hembok Ridge Drive, Suite 103  
 Village of Wilder • White River Ct. • VT • 05101  
 (802) 698-0370 • Fax: (802) 696-0374  
 cld@cldeengineers.com • www.cldeengineers.com  
 Hamner, New Hampshire • Vermont



CLIENT:  
**MOUNT SUNAPEE RESORT  
 SUMMER ADVENTURE PARK**  
 1398 RTE. 103 PO BOX 2021  
 NEWBURY, NEW HAMPSHIRE 03255

**MOUNT SUNAPEE RESORT  
 SUMMER RECREATION PROGRAM  
 NEWBURY, NEW HAMPSHIRE**  
**IMPROVEMENTS PLAN 2014  
 LOWER MOUNTAIN  
 AND BASE MAP**

SCALE: AS NOTED	PROJECT NO. 12-0111
DATE: 05/07/14	DWG. NO. AOP2014_2



- EXISTING BUILDINGS
- EXISTING ROADS
- EXISTING LIFTS



# Mount Sunapee Resort

Newbury, NH

## Summer Recreational Program Proposal



Presented to the New Hampshire  
Department of Resources and Economic Development

November 3, 2011

# **Mount Sunapee – Proposed Summer Recreational Plan**

## **Table of Contents**

### **Introduction**

### **New Summer Activities and locations**

1. Canopy Tour / Zip Line
2. Treetop Adventure Park
3. Mountain Bike Trails
4. Disc Golf
5. Interpretive Hiking Trails
6. Segway Tours
7. Miniature Golf

### **Existing Summer Activities and locations**

1. League of New Hampshire Craftsmen's Fair
2. Weddings, Receptions, Banquets & Meetings
3. Summit Dinners
4. Concerts
5. Summit Chairlift Rides

### **Location Map**

### **New Hampshire Competitors and Recent Competitive Developments**

1. Attitash
2. Bretton Woods
3. Cannon / Mittersill
4. Cranmore
5. Gunstock
6. Loon
7. Ragged
8. Waterville Valley
9. Wildcat

### **Phoenix Experiential Designs – company overview**



## **I. Introduction**

Mount Sunapee management has proposed expanding the summer recreational offerings at Mount Sunapee several times since Okemo's original *Proposal for the Operation of the Mount Sunapee Ski Area* which was submitted to the New Hampshire Department of Resources and Economic Development on April 1, 1998. (note: see Tab 4, Section N, p 70-71)

The following summer recreational activities were proposed and described with some detail in the original 1998 Okemo *Proposal*:

- Mountain Biking
- Scenic Chairlift Rides
- Hiking
- In-line Skating & Skateboard Park
- Alpine Slide
- Concerts
- Water park

Other summer recreational activities were simply listed as potential activities and included the following:

- Craft Fairs
- Athletic Events
- Weddings & Family Gatherings
- Special Ethnic Festivals
- Children's Day Camps
- Nature and Wildlife Interpretation and Education
- Archery Competition
- Food and Brewery Festivals

Since Okemo's *Proposal for the Operation of the Mount Sunapee Ski Area* in 1998, four important documents have followed including:

- April 20, 1998 Lease and Operating Agreement
- January 25, 2000 5-year Master Development Plan
- June 1, 2005 5-year Master Development Plan
- June 1, 2009 5-year Master Development Plan

In Mount Sunapee's most recent Master Development Plan which was submitted to the NH- Department of Resources and Economic Development on June 1, 2009, Mount Sunapee added a Zip Line to the summer recreational items that were proposed in the original *Proposal for the Operation of the Mount Sunapee Ski Area* and in the other two Master Development Plans.

## **II. Proposed New Summer Activities**

Mount Sunapee management has spent considerable time investigating the various attractions and options available for a summer recreational program.

Our goal has been to find the right mix of summer recreational attractions that are the best fit for our family-focused brand identity, and the best fit for the essential character of Mount Sunapee.

We found many options including attractions that have an "amusement park" feel, attractions that have a "pure adrenaline rush" feel, and attractions that have a "natural setting" feel.

Mount Sunapee managers have visited many ski areas and/or zip line operators as paid participants in New Hampshire, Vermont, New York and Massachusetts to experience the "feel" of the resort and experience first-hand the attractions offered by the operators.

Based on our experience in visiting these areas and using their various attractions, Mount Sunapee has chosen to base our summer recreational program around a "natural setting" feel which best matches our family recreational brand and the unique natural setting at Mount Sunapee.

***The following sections describe the summer recreational plans that are proposed for installation and operation in the summer and fall of 2012 at Mount Sunapee.***

## 1. Canopy Tour / Zip Line

Mount Sunapee proposes to add a Canopy Tour / Zip Line as its signature summer attraction.



The Canopy Tour / Zip Line would be located in the woods at the South Peak area.

Participants would access the start of the Canopy Tour / Zip Line by riding uphill on the 1,814 long Clipper Ship Quad chair lift which serves the South Peak trails. The vertical drop is 374 ft.

Phoenix Experiential Designs from Boone, NC is the designer of the Canopy Tour / Zip at Mount Sunapee. We plan to contract their crews for a turn-key installation beginning on May 1, 2012.

The three principals in the company have over 54 years of experience designing rope courses and challenge courses in the United States.

They have designed many rope courses at ski areas including Crested Butte, CO; Okemo, VT; Seven Springs, PA; and, Massanutten, VA.

The proposed Canopy Tour / Zip Line at Mount Sunapee would begin in the woods near the top of the Clipper Ship Quad chair lift and end behind the Learning Center building at the end of parking lot one in the base area.

To traverse the 374' vertical drop the Canopy Tour is projected to have seven (7) or eight (8) zip line stages and two features which include one aerial, Indiana Jones style rope bridge and one feature where participants rappel down to a lower platform.

The topographical map on page 7 shows the preliminary lay-out of the seven stages and two features for the Canopy Tour.

The daily capacity for the Canopy Tour is 96 people. There would be two (2) tours per hour departing on the hour and on the half-hour which is 16 participants per hour.

Prior to riding the Clipper Ship Quad chairlift, all participants will have an indoor training and safety session, and all are fitted into their safety harnesses and helmets. After arriving at the top, the first zip line is a small training line that all participants use before beginning down the Canopy Tour / Zip Line course.



Canopy Tours will typically have 8 participants with 2 trained guides in each tour. One guide leads the group across each stage, and one guide follows the group across each stage.

The length of time to complete the Mount Sunapee Canopy Tour / Zip Line layout is estimated at two hours. There are minimum and maximum weight restrictions for participants of the zip line.

The capital costs for the design and installation of the Mount Sunapee Canopy Tour / Zip is estimated at \$325,000.

We are currently in the final design stages with a turn-key installation planned to begin on May 1, 2012. Our goal is to open to the general public by the weekend of June 30, 2012.

Operations would be either 5-days a week (Wed-Sun) or 7-days a week from June 30 through Labor Day weekend, and then would operate on weekends only during the fall and winter months.



## 2. Treetop Adventure Park

In addition to the Canopy Tour / Zip Line a popular recreational offering for younger age groups is the Treetop Adventure Park.

The Treetop Adventure Park would be located at South Peak in the woods to the left of the Clipper Ship Quad base terminal.

Treetop Adventure Parks can offer several different course layouts with varying skill levels for the elements in each course.

Mount Sunapee proposes that its first Treetop Adventure Course consist of a beginner course and an intermediate skill course built together in the same overall layout.

In the future, other layouts can be added in a modular way like a clover leaf which allows participants to move from lower level courses to progressively more difficult courses without leaving the overall Adventure Park setting.



Phoenix Experiential Designs have built many adventure parks that feature rope challenge elements, and they have been selected to design the Treetop Adventure Park at Mount Sunapee.



**Typical “elements” in a Treetop Adventure Course**



Treetop Adventure Parks are very popular with younger participants who may not be able to ride the Canopy Tour / Zip Line due to being below the minimum weight requirement of 80 pounds in order to use the Canopy Tour.

Additionally, the different skills levels and height levels allow the course designer to tailor the offering to different age and ability groups.

The participants on the ropes courses are required to wear safety harnesses and are always clipped into the overhead safety line.

Prior to using the Treetop Adventure Course all participants must go through the safety training course which teaches proper use and fitting of the safety harness and of the clip-in devices.

All participants and guides wear lightweight safety helmets in the Adventure Tree Park and in the Canopy Tour / Zip Line.

### 3. Mountain Bike Trails

The Clipper Ship Quad chair lift will be the transportation vehicle for participants using the Canopy Tour / Zip Line. The Clipper Ship Quad has an hourly uphill capacity of 800 people per hour at half-speed (225 feet per minute) in summer operations.

With the capacity of the Canopy Tour / Zip Line at only 20 people per hour including guides, Mount Sunapee is interested in other recreational offerings that utilize the Clipper Ship Quad for uphill transportation given the available uphill capacity.

One such recreational activity is lift-serviced mountain biking.

This activity also fits in the natural setting, family recreation brand that Mount Sunapee has cultivated.

Mountain biking can be offered in many ways and at different skill levels. Mount Sunapee plans a low level, family oriented mountain biking experience using novice or low intermediate trails from the summit of the South Peak area.



Mountain bikes would be available for rent at Mount Sunapee.

#### 4. Disc Golf

Disc Golf offers another recreational activity that can use the Clipper Ship Quad chair lift to ride up the mountain, and play the disc golf course as they hike down the mountain.

The Disc Golf course would have a combination of "holes" that work their way down and across a ski trail, and others that weave in and out of the woods adjacent to the trails in the South Peak area.

Disc Golf Frisbees would be available for rent or purchase in the Retail Shop at Mount Sunapee.



Above is a typical Disc Golf "cup" that finishes the hole. Different Frisbees are often used for the different "shots" on the course.

## 5. Interpretive Hiking Trails

Interpretive Hiking Trails offer a recreational offering for guests in which they purchase a lift ticket to ride the Clipper Ship Quad chair lift to the South Peak summit area, and have a themed Interpretive Hiking Trail as their venue down the mountain.



The information signage would be developed around several flora and fauna categories including:

- Large Mammals
- Small Mammals
- Birds of Prey
- Song Birds
- Butterflies
- Trees
- Wildflowers
- Local history

At the head of the Interpretive Trail there may be large signage, 4' x 8' signs, which would show the trail layout and offer previews

of the locations for the many small signage locations which will show selected native species of the flora and fauna along the trail.

The Interpretive Hiking Trails would be free for guests who are willing to walk uphill to access the trails.

The Clipper Ship Quad chair lift will allow participants to enjoy riding the chair lift up the mountain for a small fee with the opportunity to enjoy the Interpretive Hiking Trail as their path down the mountain.



Along the trail would be smaller identification signage where the reflection benches are located that target species identification of the groups above.

The trails would be well marked for a defined path and may be lined with wood chips or blue stone.

## 6. Segway Tours

Segway Tours have become very popular for touring the historical sites in major cities such as Boston, MA and Manchester, NH.

They have also become very popular in natural settings as a personal touring vehicle in the base area. The ride is the thrill.

Mount Sunapee proposes having Segway Tours around the base area of the mountain along flatter elevation areas using the Segways with the larger, natural ground tires.



Riders enjoy riding through wooded areas in the base area and across parking lots such as Lot 2 or Lot 3 at Mount Sunapee.

A typical Segway Tour is 90 minutes with 6 riders and a guide.

All riders start with an indoor safety training session followed by a practice course training session before going on the Segway Tour. Helmets are provided for all participants.

## 7. Miniature Golf

Mount Sunapee has considered adding a natural setting miniature golf course for many years.

Miniature golf courses come in many designs and layouts.

Mount Sunapee proposes a ground level course that uses natural landscaping to create a scenic setting and fit into the “natural” feel of the summer recreational program at Mount Sunapee.



Miniature Golf offers summer recreational fun for all ages and is a very popular family activity that fits well with the Mount Sunapee family recreation brand.

The Miniature Golf course location poses the greatest site location challenge for Mount Sunapee. We do not have a location that is not also utilized for winter operations. We may have to make snow over the mini golf course in winter, and utilize landscaping that is recessed in pots in the ground and covered with mulch. The landscaping would be removed and stored for the winter.



### **III. Existing Summer Activities**


Mount Sunapee currently offers a limited summer recreational program. Some of the offerings include:

- Skyrides to the summit via the Sunapee Express Quad
- Summit Dinners (4) at the Summit Lodge via Sunapee Express
  - Lobster Fest
  - Family Fun Night
  - Wine Pairing
  - Beer Pairing
- Sunapee Lions Club Car Show in late June
- League of New Hampshire Craftsmen's Fair each August
- Fall Foliage Festival on Columbus Day weekend
- Weddings, Receptions, Banquets and Business Meetings

These activities will still be offered at Mount Sunapee, and the layout of the newly proposed recreational offerings will be designed to complement and not interfere with these existing activities.



#### IV. Location Map



**Approximate site location for Mount Sunapee summer recreational attractions.**

**A-J** = Canopy Tour / Zip Line stages

**TAP** = Treetop Adventure Park

**MG** = Miniature Golf

**ST** = Segway Tours

Mountain Bike Trails and the Interpretive Hiking Trails will start near the unload of Lift G (the Clipper Ship Quad) and meander through the woods and across the ski area before finishing in the base area.



## **V. NH Ski Area Competitors and Recent Competitive News**

In the past 5 years many New Hampshire ski areas have successfully introduced new or expanded winter and summer recreational opportunities and activities.

Mount Sunapee has lagged behind our competitors in recent years in introducing new summer and winter recreational activities.

Our guests are asking for more recreational offerings at Mount Sunapee as they have seen offered by our competitors.

This has been recognized by the Town of Newbury, and the Board of Selectmen are supportive of increasing the summer recreational offerings at Mount Sunapee.

The following section provides highlights of the new and expanded summer and winter recreational offerings by our NH competitors.

The section is in alphabetical order with information on the following New Hampshire competitors:

- Attitash
- Bretton Woods
- Cannon
- Cranmore
- Gunstock
- Loon
- Ragged Mountain
- Waterville Valley
- Wildcat

# Map of New England and New Hampshire ski area competitors

## Ski areas of New England

